Weekly Fire Alarm Testing Guide

sssystems
FIRE & SECURITY SPECIALISTS

Place system on Test with your ARC.

Choose the Manual Call point to test this week.

Activate chosen Manual Call point using your test key (Sounders will now activate as per your Cause & Effect programming)

Check the address and location details displayed on the Fire Panel Screen matches the Manual Call point.

Once happy the details match, press the 'Silence Alarms' button displayed on the panel screen (panel controls must be active) the Sounders will stop ringing.

Reset your chosen Manual Call point by clipping the drop down front back in place.

Once you are happy the Manual Call Point has been physically reset (can no longer see yellow strip) press 'Reset' button.

The Active device is Fire should now disappear from the Fire panel Screen

Weekly test now complete and Systems is reset